BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT16702

APPROVED SCHEDULE - B

Tender Notification EE/BTP/BBMP/E-PMT/09/2014-15, Date: 23.01.2015

Improvements to cross roads of Kodigehalli Village in ward no. 08

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of R MADHUSUDAN	
				In Figures	In Words
1	778.8	Removing B.S Slab of Drain and stacking including cost of all labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	sqm	58.0	Rupees Fifty Eight Only
2	739.86	Refixing stone slabs of drains and pointing in C.M (1:3)	sqm	75.0	Rupees Seventy Five Only
3	235.35	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides	Cum	75.0	Rupees Seventy Five Only
4	3	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @	Cum	4847.0	Rupees Four Thousand Eight Hundred Forty Seven Only
5	8.64	Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications	Cum	4773.0	Rupees Four Thousand Seven Hundred Seventy Three Only
6	14.4	Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications cement mortar 1:4	sqm	92.0	Rupees Ninety Two Only
7	2.4	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	5327.0	Rupees Five Thousand Three Hundred Twenty Seven Only
8	3.78	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-	Cum	6065.0	Rupees Six Thousand Sixty Five Only
9	2.65	Providing mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position,	Qtl	7975.0	Rupees Seven Thousand Nine Hundred
10	11.74	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface	sqm	292.0	Rupees Two Hundred Ninety Two Only
11	272.5	Scarifying existing stone metal layer upto 75mm thick along with their bituminous surface, picking up scarified materials	Sqm	82.94	Rupees Eighty Two and Ninety Four Paise Only
12	54.5	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including	Cum	1438.0	Rupees One Thousand Four Hundred Thirty
13	225	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with	Sqm	12.0	Rupees Twelve Only
14	225	Providing and applying primer coat for surfaces of medium porosity like cement stabilized soil base @ 1.10 Kg/Sqmt	Sqm	74.52	Rupees Seventy Four and Fifty Two Paise Only
15	1494	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and /	sqm	3.0	Rupees Three Only
16	1494	Providing and applying tack coat using 80/100 grade bitumen (VG10) on the prepared black topped surfaces at	sqm	18.74	Rupees Eighteen and Seventy Four Paise Only
17	49.42	KSRRB M500-18: Providing and laying semi dense bituminous concrete using crushed aggregates of specified	Cum	11070.0	Rupees Eleven Thousand Seventy Only
18	70.8	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:-	sqm	475.0	Rupees Four Hundred Seventy Five Only

19	223.58	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and	Cum	73.0	Rupees Seventy Three Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92